



2024/2025 Sanitary Lining Project

December 13, 2024



Have a Question?

Throughout the project our team will post door hangers and website updates to keep you informed. If you have questions that are not answered here, we invite you to reach out to us using the contact information provided below.

Project Contacts:

Contractor 24-hr Help Line:
(855) 845-5326

Construction Manager:
Sam Morse – City of Champlin
smorse@ci.champlin.mn.us
cityengineering@ci.champlin.mn.us
(763) 923-7105

Upcoming Sewer Maintenance

Hydro-Klean has been contracted by the city to rehabilitate the mainline sanitary sewer that your property is connected to. The rehabilitation process will include high-pressure cleaning of the public sanitary sewer and then installation of a cured in place liner inside the sewer main. The liner renews the existing sanitary sewer main to the condition of a new pipe without the inconvenience of conventional digging.

Schedule

The project will be completed in two phases. The first phase will consist of high-pressure cleaning and televising of the sanitary sewer. This work is anticipated to begin December 16th and will continue for approximately 4 weeks. There will be no impact to your sewer lateral for the pre-cleaning portion of the project. The second phase is the installation of the liner. It is anticipated that the second phase will begin approximately January 6, 2025 after the cleaning work is completed and last an additional 5-6 weeks.

The Contractor will notify individual property owners with door hangers the day prior to liner installation. **Please check your front or side doors for this notice at the end and beginning of each day.** The door hangers will notify you when the sewer liner installation is going to impact your sewer service lateral.

During this timeframe the Contractor will ask you to eliminate water usage to help prevent a sewage backups. **Please do not use bathtubs, dishwashers, or washing machines during this time.** Heavy water usage during this work could cause sewage backups within your property (until your lateral connection is cut open/reinstated). Sewer liner installation is normally completed in approximately 6 hours and once completed you can return to using water normally for the remainder of the project.

Plumbing Concerns

The sewer cleaning process uses high-pressure water that may push water out of plumbing traps and fixtures. This happens most commonly when there is a problem with the building's plumbing vent. It will be most evident by some clean water appearing around floor drains or water level rising inside of toilet bowls. If this occurs, please pour water down all floor drains or rarely used sinks, tubs or toilets to ensure that you do not have a dry sewer trap. This process will limit odors associated with the work from entering your property. **If you have any plumbing concerns during this project, you should contact the 24-hour Project Help Line at 1-855-845-5326 before calling a plumber.**

